

TOWN of PENSE
REQUEST for PROPOSAL
Concrete Sidewalk Replacement
300 Block North Front Street

PROJECT TYPE: Concrete Sidewalk Replacement

LOCATION: North side of North Front street, between Brunswick Street and Elder Street

PROJECT TIME LINE: May 1 – August 31st, 2018

1.0 INTRODUCTION

The Town of Pense is seeking a qualified contractor to replace approximately two hundred and thirty (230) lineal feet of concrete sidewalk in the Town of Pense. Exact measurements to be conducted by contractor.

The Town Foreman may be contacted at 306-501-0396 or foreman@pense.ca for any additional information regarding this project.

2.0 SCOPE OF WORK

Contractor to submit a cost, per square foot, to install four inch (4") thick sidewalk with 48" of width, where allowable.

Specifications:

1. This project shall be completed by August 31st, 2018.
2. The existing sidewalk is 8 feet wide but will be removed by the Town prior to May 1st, 2018.
3. Contractor to provide and place base fill where needed. Contractor may have to level area from which existing sidewalk is removed.
4. All base added shall be machine compacted in place.
5. Control joints shall be placed every four to five feet.
6. Concrete mix specs: 25Mpa Class C-2.
7. Contractor to form and pour concrete, to include hand excavation to establish grade and the setting of forms.
8. Contractor, Sub-Contractor or Suppliers are to avoid driving on lawns and grass areas. All damage as a result must be repaired by the Contractor.
9. Concrete shall have a light broom finish.

10. Contractor shall provide round edges on sides.
11. Contractor shall line up both ends of sidewalk to existing, as well as attach an existing sidewalk.
12. Contractor is responsible to provide security of wet concrete against vandalism and rainy conditions.
13. The Town will be responsible for restoration/landscaping along the edges of the new sidewalk once the forms are removed.
14. The Town Foreman will complete an onsite inspection at the completion of the project.
15. This project is taking place in the Town of Pense, along North Front Street, therefore traffic control is essential for the safety of all.
16. It is strongly recommended that the Bidder perform a site visit and inspection prior to RFP submission.
17. Contractor will not commence work on any weekday before 7 am and not before 9 am on a weekend day.
18. Prior to the start of work the selected contractor shall submit to the Town proof of WCB Clearance and general liability insurance coverage not less than \$2 million and naming the Town of Pense as an additional insured.
19. No information provided verbally by the Town shall be binding, nor shall it alter the requirements in any way.
20. The lowest or any quotation not necessarily accepted

3.0 SUBMISSION

One (1) completed and signed copy of the RFP Cost Schedule (Appendix A) is to be submitted no later than **11:00 am local time February 28, 2018** to the Town of Pense Administrator via mail, email or hand delivery to the Town of Pense Municipal Office located at 243 Brunswick Street, Pense, SK S0G 3W0; PO Box 125 Pense, SK S0G 3W0 or email townofpense@sasktel.net.

TOWN of PENSE
REQUEST for PROPOSAL
Concrete Sidewalk Replacement
Approx. 230 Linear Feet 300 North Front Street
Cost Schedule

COST OF LABOUR AND MATERIAL TO INSTALL 4" INCH SIDEWALK (PER SQUARE FOOT)	\$ _____
PST (6%)	\$ _____
GST (5%)	\$ _____
GRAND TOTAL	\$ _____

Company _____

Address _____

Telephone _____ Fax _____

Email _____

Name Position _____

Signature _____

Dated at _____ this _____ day of _____, 2018.

THIS PAGE MUST BE COMPLETED AND RETURNED WITH RFP

Closing Date: February 28, 2018 at 11:00 a.m.